

- 45 degree angled carparking.
- 25 stage 1 carparks (63 total) (centre of road).
- 17 of 18 existing trees retained (centre of road). 21 additional trees proposed (centre of road).
  - Centre block vehicle access removed.

One-way turnaround using existing pavement.

Remove vehicle access and topsoil, grass and plant

New timber post and rail fencing ('hurdles') to limit vehicle access to parkland while maintaining pedestrian access.

Indicative upgraded stormwater drainage.

45 degree carparking (2.6m wide x 5.4m long) as shown (total 63 carparks / stage 1 - 25 carparks) with wheel-stops.

Retain and protect all existing trees subject to arborists advice with setbacks of new pavement as shown.

Indicative scope of initial works.

Possible future street trees (indicative - subject to services setbacks, detailed design and suitable for under OH powerlines).

Centrally located concrete M-type kerb / channel with asphalt pavement on either side (where shown) to minimise earthworks within parkland.

New bollards to limit vehicle access around trees while maintaining pedestrian access.

Loading zone - suitable for heavy vehicles.

Remove vehicle access and carparking, topsoil and grass.

Possible new large-growing shade trees.

Existing poor quality tree to be removed.

Possible future footpath.

Possible future street trees (indicative - subject to services setbacks, detailed design and suitable for under OH powerlines).

Line-marked carparks.

Improved pedestrian safety with concrete footpath and connections as shown.

Retain 'informal' parking adjacent to Creswick Museum research building.

Drawing PLA565-L91 revision A issued 18/10/2023.

Indicative scope of initial (stage 1) works

- This plan is based on conceptual civil designs by Driscoll Engineering
   Services Pty Ltd and aerial photograph sourced from Nearmaps dated 9/2/2023.
- The drawings is conceptual only for consultation.
   Proposals are subject to detailed design and an arborist assessment.



- 45 degree angled carparking.
- 20 stage 1 carparks (53 total) (centre of road).
- 17 of 18 existing trees retained (centre of road). 21 additional trees proposed (centre of road).
  - Centre block vehicle access formalised.

One-way turnaround using existing pavement.

Remove vehicle access and topsoil, grass and plant

Indicative upgraded stormwater drainage.

45 degree carparking (2.6m wide x 5.4m long) as shown (total 53 carparks / stage 1 - 20 carparks) with wheel-stops.

Retain and protect all existing trees subject to arborists advice with setbacks of new pavement as shown. Indicative scope of initial works.

Possible future street trees (indicative - subject to services setbacks, detailed design and suitable for under OH powerlines).

Centrally located concrete M-type kerb / channel with asphalt pavement on either side (where shown) to minimise earthworks within parkland.

New bollards to limit vehicle access around trees while maintaining pedestrian access.

Loading zone - suitable for heavy vehicles.

New timber post and rail fencing ('hurdles') to limit vehicle access to parkland while maintaining pedestrian

Two-way roadway connection (no carparking).

Possible new large-growing shade trees.

Existing poor quality tree to be removed.

Possible future footpath.

Possible future street trees (indicative - subject to services setbacks, detailed design and suitable for under OH powerlines).

Line-marked carparks.

Improved pedestrian safety with concrete footpath and connections as shown.

Retain 'informal' parking adjacent to Creswick Museum research building.

Drawing PLA565-L92 revision A issued 18/10/2023.

Indicative scope of initial (stage 1) works

- This plan is based on conceptual civil designs by Driscoll Engineering Services Pty Ltd and aerial photograph sourced from Nearmaps dated 9/2/2023.
- The drawings is conceptual only for consultation.
   Proposals are subject to detailed design and an arborist assessment.